

CLARKE COUNTY PURCHASING  
129 RAMSBURG LANE  
BERRYVILLE VA 22611  
Phone: 540-955-5148  
Fax: 540-955-0456  
E-mail: [purchasing@clarkecounty.gov](mailto:purchasing@clarkecounty.gov)

**Clarke County  
Joint Administrative Services**

**To:** All firms interested in IFB #20-0324

**From:** Mike Legge

**Date:** March 9, 2020

**Phone:**

**Pages:** 2 total

**Re:** Addendum #001 for IFB #20-0324

**CC:**

**ADDENDUM # 001 for IFB #20-0324 BOYCE ELEMENTARY SCHOOL-ADA RAMP**

In order to answer some questions that we have received, the Clarke County Purchasing Office is posting this Addendum #001.

**Question #1: Can you please provide more direction on the paint and color for the handrails?**

*Answer #1: Ferrous Metals, Primed, Latex, 2 Coat*

- 1. Touch-up with rust-inhibitive primer recommended by top coat manufacturer.*
- 2. Semi-gloss: Two coats of latex enamel; Sherwin Williams Emerald Exterior Acrylic Latex or equal. Color: Black/Gloss Black.*
- 3. Primer(s): As recommended by manufacturer of top coats and the surface to be prepared*

**Question #2: Do the white columns on the top slab need to be altered to make room for the new concrete?**

*Answer #2: The column base shall be removed and replaced on top of the new concrete slab. The column shall be cut as required for this shift. Flashing, adhesion and touch up paint shall be to industry standard.*

**Question #3: There are vents on the left and right side of the entrance that look to be affected by the new ramp construction. What should be done with them?**

*Answer #3: The selected vendor shall block the vents (that will be effected by the construction of the new ramp) solid with CMU block prior to installation of the ramp.*

**Question #4: Can the selected vendor have access to water and power during the project?**

*Answer #4: Yes, water and power will be available to the selected vendor.*

**Question #5: Do the down spouts need to be altered in any way to make room for the new ramp?**

*Answer #5: The notes on the drawings note that the rail will clear the downspouts and that the concrete should be placed around the cast iron. The selected vendor will need to install isolation joints at the downspout locations.*

Please be sure to complete the bottom portion of this and include a signed copy with your proposal form.

+++++

PRINT, PLEASE:

Yes, I acknowledge receipt of this addendum #001 for the IFB #20-0324.

Name \_\_\_\_\_ Name of Company \_\_\_\_\_

Street Address \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

Email: \_\_\_\_\_